

TENDER DOCUMENTS



Subject: Raising of Compound Wall including Removing Iron Grills
and Re-fixing on Top of Wall

From:

**Director
National Centre of Excellence in Analytical Chemistry
University of Sindh, Jamshoro.**



National Centre of Excellence in Analytical Chemistry
University of Sindh, Jamshoro

SUBJECT: Raising of Compound Wall including Removing Iron Grills
and Re-fixing on Top of Wall

The tender contain _____ pages issued to

M/S _____ Contractor

on ____/____/2015

DIRETOR

NCEAC
University of Sindh, Jamshoro



National Centre of Excellence in Analytical Chemistry
University of Sindh, Jamshoro

BIDDING DATA

(This section should be filled in by the Engineer/ Procuring Agency before issuance of the Bidding Documents)

- a) Name & address of the Procuring agency : NCEAC, University of Sind, Jamshoro.
- b) Brief Description of Works : Raising of Compound Wall including Removing Iron Grills and Re-fixing on Top of Wall
- c) Estimated Cost : Rs. 820,155.00
- d) Amount of Bid Security : 2% (16500.00)
- e) Period of Bid Validity : 1 Month
- f) Amount of Bid Security : 10% (Rs. 82020.00) 2% at the time of submission and 8% deductible from the running bills.
- g) % if any, to be deducted from bill. : 8% (Rs. 65615.00)
- h) Deadline of Submission of Bids Along with time : Jan 07, 2015 upto 11: 00 AM
- i) Venue, Date & Time of Bid opening : NCEAC, University of Sindh, Jamshoro. Jan 07, 2015 on 1: 00 PM
- j) Time of Completion from written Order of commence : 1 Month
- k) Stamp Duty : **0.30%** Or notified by the Govt. of Sindh, will be paid by Successful bidder a stamp duty



National Centre of Excellence in Analytical Chemistry
University of Sindh, Jamshoro

SUBJECT: Raising of Compound Wall including Removing Iron Grills
and Re-fixing on Top of Wall

GENERAL ABSTRACT

1. Cost of Schedule Items	Rs. _____
Add/ Less _____ % above/ below	Rs. _____
Total	Rs. _____
Cost of Non Schedule Items	Rs. _____
Total	Rs. _____

CONTRACTOR

Schedule B

**SUBJECT: RAISING OF COMPOUND WALL INCLUDING REMOVING IRON GRILLS AND RE-FIXING ON TOP OF WALL
AT CENTRE OF EXCELLENCE IN ANALYTICAL CHEMISTRY**

Sr.	Items	Qty	Rate	Unit	Amount	
1	Removing Iron Grill (M .R.)	2375.0	25.5	Psft	60562.00	
2	Pacca Bricks work in G/F C.M (1:6)	P-20/5	1100.0	12674.36	%cft	139418.00
3	RCC Work	P-15/6(a)	450.0	337	Pcft	151650.00
4	Fabrication	P-16/8	31.6	5001.7	Pcwt	158054.00
5	Filling Iron Grills	P-93/30	2375.0	R. R. 26.50 53.32	P. Sft	62937.00
6	Cement Plaster 3/8" thick (1:6)	P-51/13	4600.0	2122.72	%cft	97645.00
7	Cement Plaster 3/8" thick (1:5)	P-51/12	4600.0	2166.72	%cft	99669.00
					PKR 769,935.00	
				Add 10% above on Items No. 4	PKR 15,805	
					PKR 785,740.40	
				Add: Cartage of Material	PKR 34,415.00	
				Total	PKR 820,155	

Assistant Engineer: _____
Engr. Allah Bakhsh Solangi

Project Director: _____
Engr. Qamar - ul - Hassan Memon

Director, NCEAC: _____
Prof. Dr. Shahabuddin Memon